

**SCHEDULE OF WORKS
PROPOSED RETAINING WALL
HERMITAGE BUILDING, KOZHENCHERRY**



IT.NO.	DESCRIPTION OF THE WORK	QTY.	UNIT IN	RATE IN FIG	AMOUNT
1	Dismantling of the existing cement block parapet manually including stacking of material within 150 metres lead as per direction of Engineer - in - charge.	14.00	CU.M		
2	Removing the earth from inside the Parapet	90.00	CU.M		
3	Dry pack rubble work inside the existing retaining wall after consolidating the earth below and keeping the top of rubble work horizontally level to act as the base for RCC Base slab	28.00	CU.M		
4	Reinforced Cement concrete M-20 using 20 mm broken stone for Retaining wall base slab including all form work, watering, curing etc. complete, including cost of reinforcement work, bend tied and placed in position using 22 gauge binding wire etc. complete	18.00	CU.M		
5	Reinforced Cement concrete M-20 using 20 mm broken stone for Retaining wall including all form work, watering, curing etc. complete, including cost of reinforcement work, bend tied and placed in position using 22 gauge binding wire etc. complete. Provide 75 mm dia weepholes at an interval of 90 cms c/c in a zigzag order	24.00	CU.M		
6	Reinforced Cement concrete M-20 using 20 mm broken stone for Parapet wall including all form work, watering, curing etc. complete, including cost of reinforcement work, bend tied and placed in position using 22 gauge binding wire etc. complete	4.00	CU.M		
7	Plastering with cement mortar 1:4 12 mm thick one coat floated hard and trowelled smooth for parapet and retaining wall including scaffolding, curing etc. complete.	270.00	SQ.M		
8	Boarder plastering with cement mortar 1:4 12 mm thick one coat floated hard and trowelled smooth for parapet including scaffolding, curing etc. complete	150.00	R.M		
9	Earth filling inside the retaining wall using available earth at site.	70.00	CU.M		
10	Earth filling inside the retaining wall using earth from outside	120.00	CU.M		

Annamma

Anna Architects
Annamma Antony
Registered Architect
Reg.No:CA/95/18292
Mob:9446115303