



MALANKARA MAR THOMA SYRIAN CHURCH

Sabha Office, Mar Thoma Sabha Secretariat,
Thiruvalla, Kerala, India-689 101

0469-2630449
2606080, 2606090

sabhaoffice@marthoma.in
www.marthoma.in

Metropolitan: Most Rev. Dr. Theodosius Mar Thoma

Ph: 0469-2630313, 2601210 (P)

Sabha Secretary

Rev. Abey T. Mammen
Mob: +91 9496071964

Clergy Trustee

Rev. David Daniel
Mob: +91 9447398155

Lay Trustee & Treasurer

Adv. Anzil Zachariah Komattu
Mob: +91 9497111110

Dt. 04-07-2025

**Invitation to Submit Quotation for Road work, R.C.C. Retaining Wall and P.C.C.
Work near Mar Thoma press building area**

Malankara Mar Thoma Syrian Church invites sealed quotations from experienced and qualified contractors for the work of our facility. The scope of work is attached below. Interested parties may contact us for further details or to arrange a site visit. All details must be clearly filled and must be sent by post to Sabha Secretary, Mar Thoma Sabha Office, Thiruvalla – 689101 or by e-mail to sabhaoffice@marthoma.in on or before 12th July, 2025 by 5:00 PM.

For inquiries or further information, please contact the Estate Officer at +91-9645276838

Yours Sincerely,



Rev. Abey T. Mammen
Sabha Secretary

Proposed road work near Mar Thoma press building area

Quotations

<u>SI No.</u>	<u>Description of work</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Earth work excavation and proposed road formation, leveling with quarry makku rates including charges for, watering, ramming and cost of all materials etc.	46.80m3		
2.	Providing PCC 1:2:4 for road work thickness of 15cms using 20mm nominal size hard granite broken stones mechanically vibrated including cost, conveyance , lead and lift of all materials to site, and cost of all materials etc	35.10m3		
3.	Dismantling the existing random rubble retaining	5.63m3		
4.	Random rubble masonry with C: M 1:8 for proposed retaining wall at height of 1.00 mtr from existing retaining wall and using C:M 1:4 for pointing on both sides of proposed retaining wall and cost of all materials etc	11.25m3		
5.	Providing solid block work in cement mortar 1:6 using for 20 cms thick drainage walls including cost, conveyance ,lead and lift of all materials and cost of all materials to site	1.25m3		
6.	Plastering with cement mortar 1: 4, 12mm thick one coat of retaining walls, including cost, conveyance ,lead and lift of all materials and cost of all materials to site	7.80m2		

27.06.2025
Thiruvalla


Sabha Secretary
Mar Thoma Sabha Office

Name and address of contractor with mob. Number
Rates are inclusive of all taxes

Proposed R.C.C retaining wall near Mar Thoma press building area


Quotations

<u>SI No.</u>	<u>Description of work</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Earth work excavation for foundation of retaining wall in all classes of soil including hard literate cutting(except which require blasting conveying and dumping the excavated soil with in the site premises including all lead and life and including charges for filling the basement with soil excavated stacked at site including charges for breaking colds, watering, ramming etc	12m3		
2.	Providing PCC 1:4:8 for retaining wall foundation thickness of 15cms using 20mm nominal size hard granite broken stones mechanically vibrated including cost, conveyance , lead and lift of all materials and cost of all materials to site.	3m3		
3.	Providing PCC 1:2:4for retaining wall base slab using 20mm nominal size hard granite broken stones mechanically vibrated including cost, conveyance , lead and lift of all materials to site,and cost of all materials etc but excluding cost of steel	3.66 m3		
4.	Providing PCC 1:2:4 for retaining vertical wall using 20mm nominal size hard granite broken stones mechanically vibrated including cost, conveyance , lead and lift of all materials to site, and cost of all materials etc but excluding cost of steel	12.30 m3		

5. R.C.C works as per design using various sizes of T.M.T bars of Grade Fe-415 including straightening, cutting, bending, tying, assembling in position and binding with 18 gauge G.I binding wire etc, including cost, conveyance, lead and lift of all materials and cost of all materials etc

700Kg

27.06.2025
Thiruvalla



Sabha Secretary
Mar Thoma Sabha Office


Name and address of contractor with mob. Number
Rates are inclusive of all taxes

Proposed yard leveling and P.C.C work near Mar Thoma press building area

Quotations

<u>SI No.</u>	<u>Description of work</u>	<u>Quantity</u>	<u>Rate</u>
	<u>Amount</u>		
1.	Earth work excavation for yard formation and leveling with quarry makku rates including charges for, watering, ramming cost of all materials etc.	75m3	
2	Providing PCC 1:2:4 with thickness of 15cms using 20mm nominal size hard granite broken stones mechanically vibrated including cost, conveyance, lead and lift of all material to site, cost of all materials etc	56.25m3	

27.06.2025
Thiruvalla


Sabha Secretary
Mar Thoma Sabha Office

Name and address of contractor with mob. Number

Rates are inclusive of all taxes