



MALANKARA MAR THOMA SYRIAN CHURCH



Head Quarters: Sabha Office,
Mar Thoma Sabha Secretariat
Thiruvalla, Kerala, India-689101



0469-2630449
0469-2606090



sabhaoffice@marthoma.in



www.marthoma.in

Metropolitan: Most Rev. Dr. Theodosius Mar Thoma
Ph: 0469-2630313

Sabha Secretary
Rev. Danial Varghese
Mob: +91 9497614948

Clergy Trustee
Rev. Dr. K. Thomas
Mob: +91 9947110145

Lay Trustee & Treasurer
Dr. Koshy Mathai
Mob: +91 9447256501

INVITING QUOTATION FOR CIVIL WORK AT VGM HALL

Sealed quotations are invited for the Civil Work at VGM Hall required for our upcoming works as per the details attached in the Quotation.

Interested parties are requested to submit their sealed quotations on or before 3PM on **28/09/2026** to the Sabha Secretary, Mar Thoma Sabha Office, SCS Campus, Thiruvalla- 689101

Contact: 0469-2630449, 2606080

Thiruvalla
19.09.2026


Rev. Danial Varghese
Sabha Secretary

BOQ for quotation

Sr. No.	Description of labour work	Unit	Qty.	Rate	Amount including GST
1	Maintenance of existing bathrooms Labour for the agreed repair schedule for two bathrooms, each assumed 40 sq ft floor area and 10 ft wall height. Include cleaning, minor regrouting, servicing existing fittings and leak testing. See scope on page 2.	No.	2		
2	Demolition of existing wall Careful dismantling of the identified wall, protecting adjoining work, stacking reusable material and shifting debris to the designated site collection point. Wall thickness and material to be recorded.	sq ft	200 approx.		
3	Plastering maintenance Remove defective plaster; clean and prepare substrate; apply compatible repair plaster to match existing thickness, profile and finish; cure and clear debris.	sq ft	200 approx.		
4	Demolition of overhead water tank Drain and isolate tank; dismantle carefully in sections; lower debris and shift to the designated site collection point. Make good disturbed connections and local finishes within the agreed scope.	Item	1		
5	Civil work of the hand wash with eight taps .Finish it with tile and Granite as per the requirement. Labour to fabricate and install one trough and supports from client-supplied materials; finish joints; fix eight taps and connect supply and waste within agreed limits; test drainage and leaks.	Set	1		

Thiruvalla
19.09.2026


Rev. Danial Varghese
Sabha Secretary